

Evaluation Component/ Sub-Component	Additional Notes and Comments
Portable Building	The free standing portable has no computer network tie. Has fire alarm devices, but not tied into main school; non-illuminated exit sign.
Site Service	Conversation with EPCOR, the existing power demand is 200 amps which represents 34% of the total service being used. To be consistent with the recommended mechanical upgrades and electrical load increase, we recommend a service upgrade to estimated 300 amp service.