

## TABLE OF CONTENTS

	Page
Executive Summary	i
Facility Profile and Summary	1
Section 1 – Site Conditions	4
Section 2 – Building Exterior	7
Section 3 – Building Interior	10
Section 4 – Mechanical Systems	13
Section 5 – Electrical Systems	20
Section 6 – Portable Buildings	24
Section 7 – Space Adequacy	25
Mini Plans	Ai
Typical Photographs	Photo page 1

### Evaluation Team

Architectural

#### Building Science Specialists

345 305 4625 Varsity Dr. N.W.

Calgary, Alberta T3A 0Z9

Phone: (403) 543-2255 Fax: (403) 241-3015

E-mail: [bssl@telusplanet.net](mailto:bssl@telusplanet.net)

Mechanical/Electrical

#### J.R. Mayor Consultant

231 Oakridge Circle S.W.

Calgary, Alberta T2V 4H4

Phone/Fax: (403) 281-8022

## **Executive Summary**

In March 2000, Alberta Infrastructure engaged Building Science Specialists to evaluate the condition of 21 schools within the Calgary Board of Education. A standardized form, developed by Alberta Infrastructure and supplied to the evaluation team by the regional coordinator was used to document the condition and recommendations.

The original building was constructed in 1956. An addition was added in 1959. Minor renovations have been made to the building, upgrading the Office and Staff Room.

The school is constructed concrete slab on grade and suspended slabs at the tunnels. Walls are wood frame with some interior concrete block and poured concrete bearing walls. Roofs are sloped or flat wood frame.

## **Summary of Observations and Recommendations**

The school jurisdiction has a roof replacement program. No reports are available for the roof and further investigation is required. The presence of hazardous materials in the building is expected in piping insulation, light ballasts and some interior finishes. These issues are dealt with as the jurisdiction undertakes upgrading. The costs associated with removing hazardous materials have not been included in any of the costing.

## **Architectural**

The exterior of the building is finished in horizontal wood siding and/or wood paneling. The upper portion of the walls is finished in stucco. Both materials require painting. Some upgrading of the play areas is necessary. Handicapped accessibility must be addressed. Some additional architectural work is required to accommodate the recommended mechanical and electrical renovations; a cash allowance has been included.

## **Mechanical**

The heating plant is original to the building and requires replacement. A ventilation system is required in the Office. A new hot water tank is required.

### **Electrical**

Additional exterior lighting and parking plugs are required. A new fire alarm system is necessary and emergency lighting requires upgrading Upgrade lighting throughout to T-8's. New lighting is necessary in the gym and stage area.

### **Costing**

The estimated construction costs for the remedial work in the attached evaluation form has been based on the Costing Unit Rate Chart developed by Alberta Infrastructure. Where this data was incomplete or inappropriate to the recommended work, unit costs based on the local Calgary market were used.

1.	Site related work	\$35,200.00
2.	Building exterior	\$115,000.00
3.	Building interior	\$31,000.00
4.	Mechanical systems	\$71,900.00
5.	Electrical systems	\$105,500.00
6.	Portables – n/a	_____
Total Estimated Costs		\$358,600.00

### **Space Adequacy**

The existing area, according to the School Building Area Guidelines and Supplement – maximum Gross Area of School Building Projects is deficient.

Existing Total Gross Area (square metres)	2769.6
Projected required total gross area (square metres)	<u>3025</u>
Overage / (Deficiency) (square metres)	(256.4)

### **Further Investigation**

Further investigation is required to determine the impact of the removal of hazardous material during any renovation work. Code related issues with respect to fire separations should be reviewed at the time of renovation. There is no report on the roof; it requires further review, as do the roof accessories.

### **School Plan Data Information**

The plan information for the building was supplied by the school jurisdiction. Area information was provided by Alberta Infrastructure. The information generally appears to be up to date with some minor room function revisions.