

"Helping Build Communities"

210, 10190 - 104 St.
Edmonton, Alberta
Canada T5J 1A7

Tel: (780) 423-6606
Fax: (780) 429-3962
barryder@caisnet.com



600 Student (5-9) Core Middle School

Design Development Short Report

File ref: 28332

February 25, 2009



TABLE OF CONTENTS

PROJECT PARTICIPANTS	1
CONCEPT OPTION IMAGES	2
1.0 CONTEXT AND FRAMEWORK FOR FACILITY DEVELOPMENT	3
2.0 PROJECT GOALS AND OBJECTIVES	4
3.0 DESIGN DEVELOPMENT	4
3.1 Program and Area Summary	4
4.0 LEED® OVERVIEW	7
4.1 Current Project Standing	7
5.0 STRUCTURAL	7
5.1 Design Criteria	7
5.2 Foundation System	8
5.3 Main Floor	8
5.4 Roof System	8
5.5 Wall System	8
6.0 MECHANICAL	8
6.1 Design Criteria	8
6.2 Fire Protection and Life Safety	8
6.3 Site Service Utilities	9
6.4 Plumbing Systems	9
6.5 Heating Systems	9
6.6 Ventilation Systems	10
6.7 Exhaust Systems	11
6.8 Humidification Systems	12
6.9 Controls	12
6.10 Executive Summary	12
7.0 ELECTRICAL	13
7.1 Design Criteria	13
7.2 Power Service and Distribution	13
7.3 Telephone Service and Distribution	13
7.4 Duplex Receptacles	13
7.5 Car Park Receptacles	14
7.6 Lighting	14
7.7 Exit Lights	14
7.8 Emergency Lighting	14

Proposed New 5-9 (600 student)
Core School

7.9	Fire Alarm and Smoke Detection System	15
7.10	Intrusion Detection System	15
7.11	Sound and Intercommunication System	15
7.12	Cable Television System	15
7.13	Computer Provisions	15
7.14	Clocks	16
7.15	Energy Conservation Features	16

APPENDICES **17**

Appendix A – AI’s Area Analysis/ Modified Area Analysis
Appendix B – Architectural Drawings
Appendix C – Design Ratios
Appendix D – LEED® Checklist

PROJECT PARTICIPANTS

Steering Committee

John Lovell
John Gibson
Fred DeMott
Brian Oakley
Laurie Douglas
Jim Patrick
Bill McCabe
Bonnie Dong
Bob Gerhardt
Pat Cox
Keith Jones
Robert Ashley
Jack Meredith
Steven Bushnell
Dino Loutas
Darryl Doucet
Wen Yan
Michael Jackson
Allan Colpitts

Organization

Alberta Infrastructure
Alberta Infrastructure
Alberta Infrastructure
Alberta Infrastructure
Alberta Infrastructure
Alberta Infrastructure
Alberta Infrastructure
Alberta Infrastructure
Alberta Education
Alberta Education
Alberta Education
Calgary Board of Education
HGBC
Barr Ryder Architects & Interior Designers
Protostatix Engineering Consultants
A.D. Williams Engineering
A.D. Williams Engineering
A.D. Williams Engineering
Hanscomb Limited

Project Team

Prime Consultants
Architectural
Structural Engineering
Mechanical Engineering
Electrical Engineering
Energy Modeler
Cost Consultant
LEED® Consultant

Barr Ryder Architects & Interior Designers
Barr Ryder Architects & Interior Designers
Protostatix Engineering Consultants
A.D. Williams Engineering
A.D. Williams Engineering
A.D. Williams Engineering
Hanscomb Limited
HGBC

CONCEPT OPTION IMAGES



1.0 CONTEXT AND FRAMEWORK FOR FACILITY DEVELOPMENT

The Grade 5-9 (600 student) Core Middle School design meets Alberta Education Program requirements for this size of school. In addition to supporting the appropriate education of children, the facility must ensure their wellbeing, both inside and outside of school.

As the core school concept incorporates a percentage of classrooms as modular relocatables, it is essential to the evolution of the school that the incorporation of modular classrooms is integral to the functioning of the school, providing first class teaching areas within the school.

Finally, the Grade 5-9 (600 student) Core School is designed to meet or exceed the requirement to achieve LEED® Silver certification.

As part of our design process, the following philosophical goals were established as the basis by which the design of the Grade 5-9 (600 student) Core School evolved:

- A school designed to meet all programmatic, educational and Alberta Infrastructure requirements based on:
 - The School Infrastructure Manual (SIM)
 - Design and Construction Standards and Guidelines for School Facilities (Green Book)
 - The Alberta Infrastructure Design Ratio Guidelines
 - Alberta Educational Funding Allowance
- Develop a Core School with modular relocatable classrooms providing equivalent facilities to a permanent school of identical capacity.
- Develop a simple circulation system with clear lines of visibility and orientation for maximization of supervision and security.
- Develop flexible learning and interactive spaces for students, teachers and the community.
- Make provision for variability of components within the core to suit individual school board requirements.
- Create an ability for the facility to be separated into wings for appropriate separation of programs as deemed appropriate for the size of the school and age classifications.
- Establish simple and cost effective building system, structural, mechanical and electrical systems within the Alberta Infrastructure guidelines, including the incorporation of the *‘‘PERSIST’’ wall system.

- Incorporation of sustainable design systems into the building concept as deemed practicable including the maximization of natural lighting and views and achieve LEED® Silver Certification.

*Pressure Equalized Rain Screen Insulated Structure Technique

2.0 PROJECT GOALS AND OBJECTIVES

The overall planning goal for the standardization of the Grade 5-9 (600 student) Core Middle School design focused on several key areas:

- Flexible use of space.
- Facilities that enhance learning.
- Simple and effective structure and systems to ensure “best value” for money.
- Safe and accessible environment for learning.
- Incorporation of the modular classrooms into the school.
- The maximization of community access to community use facilities (i.e. gymnasium).
- A design that reflects responsible stewardship.

3.0 DESIGN DEVELOPMENT

3.1 Program and Area Summary

Total Target Area for the Grade 5-9 (600 student) Core Middle School:

• Core Area		4,247 m ²
• Modular Classrooms	12 @ 100 (+/-)	<u>1,200 m²</u>
Total Build-out Gross Area		5,447 m ²

.1 Site

Based on a generic site concept, the following fundamental site development guidelines have been established:

- .1 The orientation of the building should be towards the street:
 - Identifiable presence in the community.
 - Ease of front entry identification and orientation.
 - Clear site lines and visibility for security.
- .2 Student access should be from the main road.
 - Student safety and site security is paramount.

- .3 Student drop off areas for both cars and buses should be directly off the main road.
 - Separate drop off areas to be identified for both buses and cars.
 - Drop off areas on the main access, reduces the impact of large separate passenger and bus drop off areas.
 - There should be limited opportunity for pedestrian traffic to conflict with vehicular traffic.
- .4 Student drop off areas to be separated from parking area.
- .5 Student playground areas should be oriented to the rear of the school.
- .6 It is also essential to the development of the site that the orientation of the facility enhances the sense that this new building is part of the community and the community are welcome.
- .7 Staff and visitor parking areas to be located away from congested student drop off areas, but adjacent to the school.

.2 **Building**

The initial prototype Core School was to be designed based on a total occupancy of six hundred (600) students. Based on information provided by Alberta Infrastructure the total allowable gross area for the Core School including relocatables was not to exceed 5,447 m².

The programmed areas as provided by Alberta Infrastructure outline that to accommodate 600 student (5-9) Core Middle School is to include:

- 12 modular relocatable classrooms;
- three science labs/classrooms;
- four ancillary classrooms;
- CTS labs/classrooms;
- a gymnasium;
- a library;
- two information service areas;
- an administration area;
- washrooms, and;
- a variety of service and support areas.

A detailed area breakdown for the school is included in **Appendix A**.

All the programmatic, educational and accessibility requirements are to be met in the design of the Core School. At this time, some assumptions are made as to programmatic details, however, the flexibility of the design allows for refinement during the client and stakeholder review process and workshops.

The administration area, library and gymnasium are located off of the central gathering space for equal common and secure access.

It is essential that the administration suite be visually and physically accessible as one immediately enters the school. A sense of welcome, but also a sense of security needs to be maintained at all times. The proposed two-wing concept for the school allows for a high degree of visual and secure access from the administration suite and gathering node.

The proposed gymnasium also oriented on the main entry axis of the school is intended to be a two-station gymnasium complete with a retractable divider curtain. The gymnasium will offer full competitive basketball and volleyball courts, gross court basketball and volleyball and badminton courts. It was important to the overall design team that the new gymnasium accommodates the many community-enhancing programs desired for the School. After hour's sports programs and community gatherings were all desired uses for the gymnasium.

The two permanent wings of the School support each pod of modular relocatable classrooms. The wings house the various core areas demanded by the programmatic requirements of the divisions of the school. The modular relocatable classroom pods are to be established based on the population base of each location. The groupings of each modular pod can also be modified as the individual demographics of each school change.

Acoustic treatment should be provided and incorporated throughout this facility. All spaces will have to be designed to achieve and maintain the minimum acoustic standards as prescribed in Alberta Infrastructure Design and Construction Standards and Guidelines for School Facilities.

The modified Area Analysis for this Grade 5-9 (600 student) Core Middle School design is included in **Appendix A**.

.3 Building Scale and Details

As this School is a Grade 5-9 (600 student) Core Middle School facility, the design team felt it was essential that the new Core School presented a scale that was appropriate to the age group and the community. The entry is at a scale and appropriate for this type of public building within the community. The proposed building concept also allows for an increase in the scale of the spaces as one progresses into the building and into the more public spaces. The circulation node/gathering space adjacent to administration commands a larger presence in the building, while the gymnasium is aesthetically and functionally the tallest space in the facility.

Light and views also play a significant role in the development of this facility. All teaching and occupied spaces will receive appropriate levels of natural lighting. Exterior windows would be operable for access to fresh air.

Areas like the main entry circulation node/gathering space will receive clerestory lighting accents.

.4 Exterior Elevations Concept

It is important that the School reflect an appropriate scale for a middle school. Colors and materials are used to break the scale of the school, reflect a neighborhood scale, conform to any architectural controls, and personify durability and longevity.

The configuration of the school allows for a variety of entry accents and façade accents along the exterior of the permanent school, including student entrances to the playground areas. Some of these options have been included in this report.

Masonry is to extend from the floor level to 3m to ensure exterior durability for the school. A combination of Hardiboard panels and pre-finished metal siding is to be incorporated into the school to unify the modular classrooms and break the mass of the school.

4.0 LEED® OVERVIEW

At the onset of the project, it was established by Alberta Infrastructure and Transportation that the standard core elementary schools be designed to target sufficient LEED® points so that once a project site is identified, LEED® Silver under LEED® Canada – New Construction, V1, is attainable.

4.1 Current Project Standing

The LEED® scorecard currently indicates a LEED® Silver standing at 39. This assessment reflects only the content incorporated into the Design Development Report and the credits that appear well within reach assuming current initiatives are completed. Items discussed as potentially viable for this project but which cannot be confirmed from information in the Design Development Report are itemized under the “*may be or ?*” column. There are currently 10 credits in this column. A full LEED® checklist has been provided in **Appendix D**.

5.0 STRUCTURAL

5.1 Design Criteria

The structural design will be in accordance with the following codes and standards:

- Alberta Building Code 2006
- National Building Code 2005
- Structural Steel Design CAN/CSA-S16-01
- Reinforced Concrete Design CAN/CSA-A23.1 / A23.2 / A23.3
- Engineering Masonry Design CSA-S304.1

5.2 Foundation System

A geotechnical investigation must be completed for each proposed site, to determine foundation type; however, foundations will either be a foundation wall on footing system or a grade beam on pile system. If concentrations of soluble sulphates are present in the soils, Portland Cement Type 50 will be utilized for all foundation concrete.

5.3 Main Floor

Pending final geotechnical recommendations, a reinforced cast-in-place concrete floor on grade will be provided for the main floor.

The floor will consist of 130 mm reinforced concrete slab unless noted otherwise in the soils report, resting on compacted 150 mm clean well-graded granular base over native soils below.

Cast-in-place concrete structural supported floors will be provided for all exterior concrete stoops at doorways and any other areas, which may be designated as “sensitive to movement”.

5.4 Roof System

The roof structure over the new schools will consist of a combination of steel deck supported by steel joists, beams, and steel trusses. Acoustic steel deck will be utilized over the Gymnasiums.

5.5 Wall System

Steel beams supported by a series of steel columns will be utilized to support the roof loads mainly along the perimeter and corridor walls.

6.0 MECHANICAL

6.1 Design Criteria

The mechanical design will comply with the current *Alberta Building Code* (2006) Model National Energy Code for Buildings (1997), and all applicable Provincial and Municipal Codes. Good quality mechanical systems will be used throughout the project. ASHRAE will be used as a guide to establish criteria for heating and ventilation system design.

6.2 Fire Protection and Life Safety

All systems shall satisfy the latest building code and NFPA requirements. The building will be fully sprinkled to NFPA 13 regardless of combustibility. In general, protection levels will be to Light Hazard with Ordinary Group 1 and Group 2 Occupancies, unless otherwise directed by the ‘Authority having jurisdiction.’ The sprinkler system will be a wet pipe quick response system. Dry heads will be provided for locations where potential freeze conditions are possible, such as vestibules. The sprinkler system will be extended from the core school into the modular classrooms. Recessed sprinkler heads will be installed in all ceiling areas and wire guards will be

provided over the sprinkler heads in the gymnasium. Grooved fittings are allowed only in fire protection systems. Extinguishers will be distributed in recessed cabinets, consistent with *Alberta Building Code (2006)* requirements.

6.3 Site Service Utilities

New storm and sanitary services are to be provided based on the generic site plan. Lines will be connected to the municipal utilities, and the site will be subject to local Guideline requirements. Storm water ponding may be required in the new green space adjacent to the new facility for storm water retention, if mandated by local Municipal requirements.

A new gas service will be provided, as required, to suit the building loads and future modular portable classroom loads.

6.4 Plumbing Systems

All new plumbing systems are to be of the latest design and of the highest degree of water consumption efficiency. Ultra low flow urinals and low flush toilets will be utilized as a sustainable design measure as a further water conservation measure. An emergency eyewash station with a tempered water supply will be provided within the infirmary. CTS rooms will have an oversized sink with an interceptor. Non-freeze hose bibs will be provided around the building for cleaning only.

Domestic hot water for the facility is to be provided by the high efficiency water heaters installed in the mechanical room. A small, domestic hot water recirculation pump will be provided to ensure the availability of hot water throughout the facility. All domestic hot, cold, and recirculation piping will be thermally insulated for energy conservation. Domestic hot, cold, and recirculation piping will be extended to all fixtures. Domestic water piping, sanitary drainage piping and natural gas piping will be extended from the core school to serve the modular classrooms. Type L copper pipe will be installed for the cold water system. Type K copper pipe will be installed for the hot water and recirculation systems. Grooved fittings will not be installed in the domestic water system.

A system of sanitary drains and venting will collect sanitary waste and transfer effluent to the municipal sewer system. The primary connection point will be a sanitary manhole in the municipal services.

Storm water will ultimately be directed to a municipal storm water system. Consideration is being given to a storm water retention system. Storm water may be collected by a system of roof drains and catch basins.

6.5 Heating Systems

The heating system for the building will be a combination of perimeter baseboard heating and/or passive radiant heating panels suspended from the structure. These perimeter elements will be a two-pipe reverse return heating water piping system. The perimeter panels will be controlled in concert with the air system functions for the building.

The orientation of the heating system will be as follows:

- Two hot water high efficiency heating boilers will be situated in the mechanical room. One exchanger will be provided for the air system glycol heating loop.
- The respective heating loops, hydronic circulating pumps, expansion tanks, and accessories will be installed locally in the mechanical room.
- A network of insulated reversed return hot water supply and return lines running to heating risers and mains will distribute heating water to the facility.
- Radiant panels will be zoned on an exposure basis. Each zone will be controlled by thermostats and 2-way control valves and where appropriate, individual room control.
- Entrance unit heaters will be ceiling or wall mounted in vestibules and entryways to allow for the offsetting of infiltration at the door entrances.
- The proposed system will provide the occupants with a high level of thermal comfort with a passive and quiet delivery of radiant energy to the building structure. This system will afford the appropriate level of zoning and controls to suit space requirements.
- Boiler plant will be controlled via a dedicated boiler controller and interface with the BMS.
- Butterfly valves will not be installed in the heating system.
- Schedule 40 steel pipe will be installed for the heating system.
- Grooved fittings will not be installed in the heating system.

6.6 Ventilation Systems

The main building ventilation systems will consist of two indoor air systems situated in the mechanical room and mezzanine. The classroom and office area systems will be designed with the premise of providing displacement ventilation at reduced air change rates, and with higher proportions of outdoor air so that fan energy consumption and duct sizes can be reduced. The gymnasium system will utilize duct mounted diffusers and will draw return/exhaust through the washroom/change rooms. All systems will be equipped with a return fan, isolation dampers, filter bank, glycol heating coil supplied from the heat exchangers, wet media humidifier, enthalpy wheel or heat pipe, and a draw-through supply fan. All components will be selected for a life expectancy of 30 years based on ASHRAE standards.

Ventilation to the classroom areas will be 100% outdoor air, displacement ventilation system to supplement the operable windows in the building. This distribution system would supply air around the perimeter of each floor to afford the minimum ventilation supplied to the spaces. *Alberta Building Code* (2006) requirements establish the minimum level of mechanical ventilation. True laminar displacement relies on thermal stratification to effectively pump out all contaminants. Hence, on a continual basis, a slow flow of 100% outside air continually passes

occupants on a continual base without drafts or dead spots. The air flow supplied to the classroom areas will not decrease the comfort levels, as schools will not be occupied during the summer months. Alternative strategies include opening the windows, drawing the blinds closed during days of higher temperatures, and allowing fresh air to circulate through the building. Ventilation to the office and administration areas will be mixed ventilation through the use of coils to increase the temperature and provide the required increased air flow with re-circulated air. Free cooling is accomplished by opening the windows to provide natural ventilation.

All air systems will utilize heat recovery systems on the facility exhaust air streams to improve operating efficiency and serve to preheat the outdoor air for the new building ventilation systems. Air systems will be equipped with a variable temperature with space temperature feedback to reset the discharge air temperature. Air systems will be designed to use 100% outdoor air and provide free cooling when outdoor conditions permit.

Wet media humidifiers will be utilized to provide humidification during the winter months in the classroom/office and gymnasium air systems. Humidifiers will be mounted in the mechanical rooms or air systems.

Air system filtration on all units shall be two stage and meet MERV 13 for LEED® compliance and air quality control.

All outdoor air and exhaust air dampers shall be insulated and utilize motorized dampers.

6.7 Exhaust Systems

The exhaust system for the washrooms in the building consists of a network of exhaust ductwork connected to the primary exhaust fans. The washroom exhaust air will not be combined with other exhaust/return air, other than at the inlet to the fan. The exhaust requirement will be in compliance with the *Alberta Building Code* (2006). Exhaust systems will also be provided for the photocopier and lunch/kitchenette areas, as well as for specific science classrooms.

Representative areas that will be equipped with ducted exhaust systems to fans are as follows:

- Science labs.
- Washrooms, change rooms and janitor rooms will be exhausted at the rate of 2 CFM/ft², as required by Code.
- Storage areas will be exhausted at the rate of 4 ACH.
- Server areas will be exhausted as dictated by the exhaust hood design.
- Fume hoods, kiln exhaust hoods, and dust collectors will be provided for Science Rooms, Art Rooms and CTS/Wood Shop. Non-recirculating dust collectors will be installed and that provision for make-up air will be provided. Overhead exhaust hood will be designed for the stoves and exhausted to the outside.

6.8 Humidification Systems

Humidity control will be provided for the core building. It has been suggested that a minimum amount of humidity control be provided using a wet media humidifier in the air systems to maintain a minimum of 15% humidity in the building during the winter months. This is a more energy efficient and resource limiting system for humidification and free cooling. The relative humidity will be variable, dependent on outside air conditions above 5°C. Humidity will be added only to the up air systems, not to the individual rooms. A water softener will be provided where the supply water requires pretreatment to meet the needs of the wet media humidifier.

6.9 Controls

The control system shall be BACnet compliant DDC energy management control system. The proposed system of room temperature control is simplistic and affords a reasonable level of temperature control. It is recommended that this system be DDC based, flexible to function, and expandable.

6.10 Executive Summary

The proposed development of the facility is driven by an optimal balance of comfort and efficiency. The intent is to provide a sustainable and environmentally conscience system design for the facility. Therefore, the following highlights are considered:

- Improvements to plumbing facilities and fixtures to improve water use efficiency and functionality.
- Improvements to heating systems for control and heat distribution management to ensure blanket coverage or exterior zones.
- Addition of mechanical cooling systems in the form of unitary systems where supplemental cooling is required.
- Addition of heat recovery systems to reduce outdoor air heating loads.
- Ventilation systems improvements to ensure low level displacement ventilation air is accurately and unobtrusively delivered to occupied spaces that can be further enhanced by the use of operable windows.
- Improvements to life safety systems to meet the minimum Code requirements.
- Addition of minimal humidification control for occupant comfort in the building.
- Using wet media humidifier to provide evaporative cooling during summer season.

7.0 ELECTRICAL

7.1 Design Criteria

This report is based on the Alberta Infrastructure Standards for Core Elementary School Facilities and the current edition of the *Alberta Building Code* (2006), Canadian Electrical Code, and all Provincial and Municipal Codes. The electrical design shall include fixtures to minimize and control energy consumption consistent with LEED® performance criteria.

7.2 Power Service and Distribution

Service will be provided underground through a utility company network, to a pad mounted transformer located adjacent to the building. From this transformer, an underground 347/600V, three phase, four wire secondary power service will be provided to the electrical distribution center located in the main electrical room. A new 400 amp 347/600V, 3 ϕ , 4 wire service will be complete with:

- 400 amp three pole main breaker.
- TVSS unit.
- Utility current transformer section/utility meter.
- Integrated digital meter.
- Moulded case thermal/magnetic breakers for the control of branch circuit panels.

The exact service size is to be confirmed during detail design. The branch circuit panels will be located throughout the school to serve the various areas of load concentration most effectively. Power, data, security, sound, and fire alarm provisions will be provided for in the corridor serving the modular classrooms.

7.3 Telephone Service and Distribution

Located in the same trench as the power service, TELUS facilities off site will provide an underground telephone service (100 mm conduit). This service will terminate in the computer networking room, with an additional 100 mm conduit provided for the supernet cable. A cable tray system will be provided through the school to serve outlets in offices and classrooms. The tray will extend down the corridor serving the modular classrooms.

7.4 Duplex Receptacles

Duplex receptacles will be provided throughout all areas of the school, for staff convenience and ease of facility operation. Special consideration will be given to the following areas: science rooms, music and arts room, CTS, and auxiliary spaces to ensure that sufficient duplex receptacles are provided to meet the special requirements of those areas. The exact location and quantity of duplex receptacles in all areas will be determined by equipment layouts.

7.5 Car Park Receptacle

Pre-manufactured, mounted post car park receptacles will be provided in the parking lot, which can be readily removed for maintenance and/or replacement. These receptacles will be controlled from the mechanical BMCS system. The control strategy of the receptacles shall be based on external temperatures with a cyclic operation.

7.6 Lighting

Fluorescent lighting will be the primary source of illumination throughout the school. LED and compact fluorescent lighting will be used in selected areas for display and feature lighting for architectural elements, or as a means of changing the aesthetics of an area. The primary light fixtures will be a 1,220 mm pendant direct/indirect linear fluorescent and a 610 mm by 1220 mm, with a recessed refractor lensed fluorescent luminaire for the school. Energy efficient T5 and T8 lamps and electronic ballast will be used in order to reduce energy consumption. Gymnasium luminaires will be surface mounted and will be equipped with energy efficient T5/HO lamps and electronic ballast. All lighting in classrooms and offices, will be controlled using low voltage switching. Corridors and gathering areas will be centrally controlled, with low voltage switches. Multi-level control will be provided in all classrooms to allow illumination levels that vary with changing tasks. Multi-level control in classrooms shall consist of one switch for the row adjacent to the whiteboard and one for the entire room. Daylight sensors will be provided for fluorescent lighting controllability and will adjust automatically with the amount of natural light within each classroom.

Exterior site lighting will be provided at exits, pedestrian walkways, and throughout parking areas. Site lighting will be designed to the illumination levels set forth by the Illuminating Engineering Society of North America. All exterior lighting will be Dark Sky compliant. Site lighting fixtures will be controlled through the use of photoelectric cells with override using the BMCS system. Low use entrances will be illuminated with incandescent fixtures complete with motion sensor and daylight controls. Selected light fixtures within corridors will be controlled from the security key pad to turn lights on during non-operational school hours to allow for personal travel.

Occupancy sensors will be utilized in storage, washrooms, and service rooms. Taking into account the natural light level, daylight sensors will be incorporated to reduce illumination levels in high ceiling areas. Lighting will be designed to achieve less than 1 watt/ft² of lighting power density.

7.7 Exit Lights

LED type Exit lights will be provided throughout the school.

7.8 Emergency Lighting

Emergency power battery packs and remote heads utilizing self-test technology will be distributed throughout the school in accordance with the requirements of the *Alberta Building Code* (2006). Emergency lighting shall include all hardware, wiring, programming and testing.

7.9 Fire Alarm and Smoke Detection System

A fire alarm and smoke detection system, utilizing current addressable technology, with horn strobes and isolation modules will be provided. The location of all devices will be as per the current *Alberta Building Code (2006)*. The Fire alarm and smoke detection system shall include all hardware, wiring, programming and testing.

7.10 Intrusion Detection System

An intrusion detection system and access control will be provided, consisting of an entry key pad at the main entry to the school as well as motion sensors in the vestibules and corridors. This system will be zoned to allow for community functions. The system shall be supplied with an auto dialer for connection to an outside monitoring facility. An electric locking system will be provided for all exterior doors and doors indicated in the architectural door schedule. Electric locking system shall be compliment with the Alberta Building Code and not limit egress under a fire alarm, power failure or other panic condition.

7.11 Sound and Intercommunication System

A telephone and intercom system will be provided consisting of a digital PABX type exchange, complete with auto attendant, voice mail and homework hot line features. Administrative handsets will be provided in the office and library and individual handsets in each classroom. The system will allow communication between all handsets and selective directing of incoming and outgoing telephone calls. Handsets will be accessible through the paging system. A paging system will be provided complete with amplifier and zone control to permit paging via telephone-intercom handset into classroom and various zones within the school. All corridors and instructional areas will be provided with overhead speakers. Bus loading area, building perimeter and playground areas will be covered by exterior speakers. A central programmable time clock for classroom signals will be provided and interfaced with the paging system. An independent sound reinforcement system will be provided for the gymnasium

7.12 Cable Television System

An underground television service (100 mm conduit) from an off site facility, will be provided for and will run in the same trench as the telephone and supernet services. A television distribution system will be provided throughout the school. The RG6-FT4 cable will be routed through the cable tray to wall outlet locations. Classrooms, project centres, breakout, conference rooms, library, staff lounge, and the gymnasium will be furnished with television outlets. The cable television system shall include hardware, wiring, programming and testing.

7.13 Computer Provisions

Computer outlets will be allocated in all instructional space throughout the school, complete with cable tray distribution in the corridor ceiling space. Category 6 cabling with 8P8C connectors will be provided. Eight computer ports will be provided for in each instructional space. Two computer outlets will also be provided for at the teacher station. One at the front of each classroom for smart board use and another in the classroom ceiling for projector use. The core school will have provision for wireless transmitters.

7.14 Clocks

Wireless analogue GPS clocks will be utilized in the classrooms and hallways. Wireless 12" diameter classroom clocks with built in antennas and transmitter/receiver will be provided in instructional and administration areas. The 15" diameter GPS clock in the gymnasium will require a wire guard.

7.15 Energy Conservation Features

In an effort to minimize and control energy consumption, provide a sustainable, efficient, and functional system for the facility that is consistent with LEED® criteria, it is proposed that the following special features be incorporated into the electrical systems of the school:

- Energy efficient lamps and ballasts.
- Multi-level local lighting controllability.
- BMCS control of car park receptacle operation.
- Use of fluorescent T8 and T5 technology.
- Occupancy sensor control of lighting in all washrooms and daylight control of corridors.

Appendices

Appendix A – AI's Area Analysis/Modified Area Analysis

		No.	Required Area (m ²)	Total (m ²)	Proposed Area (m ²)
1.0	INSTRUCTIONAL AREA				
.1	Classrooms	2	80	160	167
.2	Science Lab/Classroom	3	120	360	340
.3	Ancillary				
	• Small	3	90	270	263
	• Large	1	130	130	119
.4	Information Services	2	115	230	227
.5	Gymnasium	1	595	595	599
.6	Gymnasium Storage	1	60	60	47
.7	Library	1	240	<u>240</u>	<u>237</u>
	Subtotal (Instructional Area)			2045	1999
2.0	NON-INSTRUCTIONAL AREA				
.1	Administration	1	427	427	449
	• Principal's Office	1	15	19	
	• Vice Principal's Office	1	12	16	
	• Administration	1	20	20	
	• General Administration	1	45	60	
	• Conference	1	30	20	
	• Counseling	2	30	16	
	• Staff Lounge	1	45	47	
	• Staff Work	1 – 2	40	47	
	• Washrooms (Male)	1	4	5	
	• Washrooms (Female)	1	6	5	
	• Infirmary	1 – 2	40	18	
	• Kitchen	1	20	16	
	• Mechanical	1	120	164	
.2	Physical Education/Change	1	130	130	95
.3	Storage Area	1	108	108	90
.4	Washrooms	1	72	72	118

.5	Wiring Network	1	40	40	48
.6	Circulation Wall Area Flexible Space	1	1025	<u>1025</u>	<u>1058</u>
	Subtotal (Non-Instructional Area)			1802	1831
3.0	CAREER AND TECHNOLOGY STUDIES				
.1	CTS	2	200	<u>400</u>	<u>367</u>
	Subtotal (Career and Technology Studies)			400	367
	Subtotal (Core School)			4247	4247
4.0	MODULAR CLASSROOMS				
.1	Modular Classrooms	12	100	<u>1200</u>	<u>1200</u>
	Subtotal (Modular Classrooms)			1200	1200
	TOTAL (Combined Areas)			5447	5447

Appendix B –Architectural Drawings

SITE INFORMATION

Building Area = 4,247 SQ.M
 Site Area = 17,721 SQ.M
 Site Coverage = 24%

Overall Future Built Out
 Building Area = 5,447 SQ.M
 Site Coverage = 30%

BUILDING CLASSIFICATION

GROUP A, DIVISION 2, UP TO 6 STOREYS, ANY AREA, SPRINKLERED

1) A building classified as Group A, Division 2, that is not limited in building area, is permitted to conform to Sentence (2) provided:
 a) except as permitted by Sentences 3.2.2.7(1) and 3.2.2.18(2), the building is sprinkled throughout, and
 b) it is not more than 6 storeys in building height

2) Except as permitted by Article 3.2.2.16., the building referred to in Sentence (1) shall be of non-combustible construction, and
 a) floor assemblies shall be fire separations with a fire-resistance rating not less than 1 hour
 b) mezzanines shall have a fire-resistance rating not less than 1 hour, and
 c) loadbearing walls, columns and arches shall have a fire-resistance rating not less than required for the supported assembly.

BUILDING FIRE SAFETY
 3.2.2.27. GROUP A, DIVISION 2, UP TO 2 STOREYS, SPRINKLERED

1) A building classified as Group A, Division 2 is permitted to be of combustible construction or non-combustible construction, used singly or in combination, provided
 a) except as permitted by Sentences 3.2.2.7.(1) and 3.2.2.18(2), the building is sprinklered throughout,
 b) it is not more than 2 storeys in building height, and
 c) it has a building area not more than
 i) 2400m² if 1 storey in building height with no basement
 ii) 1200m² if 1 storey building height or
 iii) 600m² if 2 storeys in building height.

LANDSCAPE REQUIREMENTS (City of Calgary)

Setback Area: 500M²
 Minimum Required Trees: 9
 Trees Provided: 12

Exact number of trees will change based on individual site requirements


PARKING CALCULATION (City of Calgary)

Parking Stalls Required
 Junior High
 Grade 5 to 6=1 stall per 15 students =15 Parking Stalls
 225 Students
 Grade 7 to 9=1 stall per 18 students =21 Parking Stalls
 375 Students
 Total =36 Parking Stalls

Bicycle Parking Required
 600 Students x 10% = 60 Bicycle Spaces Required
 # Employees x3% = 1 Bicycle Spaces Required
 =63 Bicycle Spaces Provided


On Site Drop Off
 2.5 Stalls per 100 Students=15Required=15 Spaces Provided
 Refuse Area = 2 Bins Required (28 Sq. M.)

NOTE:
 Setbacks based on City of Calgary, requirements to be determined on a site by site basis.




**600 STUDENT CORE-MIDDLE SCHOOL
 SITE PLAN**

SCALE NTS
 DATE NOV.05,2008




ARCHITECTS
 & INTERIOR
 DESIGNERS



MAIN FLOOR PLAN
SCALE= 1:500

600 STUDENT CORE-MIDDLE SCHOOL MAIN FLOOR

SCALE 1:100
DATE NOV.05,2008



ARCHITECTS
& INTERIOR
DESIGNERS



MAIN FLOOR PLAN
SCALE= 1:500

600 STUDENT CORE-MIDDLE SCHOOL MAIN FLOOR


SCALE 1:100
DATE NOV.05,2008



Alberta
Infrastructure


ARCHITECTS
& INTERIOR
DESIGNERS

KEYNOTES:			
1	PREFINISHED CONCRETE MASONRY - COLOUR #1	10	PREFINISHED HARDIE BOARD EXTERIOR WALL COLOUR #2
2	PREFINISHED CONCRETE MASONRY - COLOUR #2	11	PREFINISHED FASCIA METAL CLADDING
3	PREFINISHED CONCRETE MASONRY SHOULDER BLOCK - COLOUR #2	12	ANODIZED ALUMINUM GLAZED EXTERIOR DOOR
4	PREFINISHED EXTERIOR METAL WALL CLADDING	13	INSULATED HOLLOW METAL DOOR c/w PRESSED STEEL FRAME
5	DOUBLE GLAZED, THERMALLY BROKEN ANODIZED ALUMINUM CURTAIN WALL EXTERIOR WINDOW U VALUE=5.91 W/M2 R VALUE=1.47 (based on Ashrae HOF 2001)	14	EXTERIOR WALL ACCENT FOR SCHOOL SIGNAGE
6	PREFINISHED PARAPET METAL CAP FLASHING w/ COUNTER FLASHING	15	STANDARD PORTABLE CLASSROOMS
7	PREFINISHED TRANSLUCENT WALL SYSTEMS ABOVE CLERESTORY LEVEL COMPLETE WITH RAIN SCREEN SYSTEMS	16	PORTABLE CLASSROOM STAIR c/w METAL RAILING
8	DOUBLE GLAZED, THERMALLY BROKEN ANODIZED ALUMINUM CURTAIN WALL EXTERIOR WINDOW AT ENTRY U VALUE=5.91 W/M2 R VALUE=1.47 (based on Ashrae HOF 2001)	17	PRESERVATIVE TREATED PLYWOOD EXTERIOR SKIRTING
9	PREFINISHED HARDIE BOARD EXTERIOR WALL FINISH COLOUR #1	18	PORTABLE CLASSROOM WINDOW
		19	PORTABLE CLASSROOM EXIT DOOR
		20	PORTABLE CLASSROOM R.W.L.
		21	PREFINISHED CONCRETE MASONRY - SMOOTH FINISH BALL WALL - COLOR #1



FRONT ELEVATION

SCALE=1:300




LEFT-SIDE ELEVATION


SCALE=1:300

600 STUDENT CORE-MIDDLE SCHOOL ELEVATIONS

SCALE 1:300
DATE NOV.05,2008




KEYNOTES:	
① PREFINISHED CONCRETE MASONRY - COLOUR #1	⑩ PREFINISHED HARDIE BOARD EXTERIOR WALL COLOUR #2
② PREFINISHED CONCRETE MASONRY - COLOUR #2	⑪ PREFINISHED FASCIA METAL CLADDING
③ PREFINISHED CONCRETE MASONRY SHOULDER BLOCK - COLOUR #2	⑫ ANODIZED ALUMINUM GLAZED EXTERIOR DOOR
④ PREFINISHED EXTERIOR METAL WALL CLADDING	⑬ INSULATED HOLLOW METAL DOOR c/w PRESSED STEEL FRAME
⑤ DOUBLE GLAZED, THERMALLY BROKEN ANODIZED ALUMINUM CURTAIN WALL EXTERIOR WINDOW U VALUE=5.91 W/M2 R VALUE=1.47 (based on Ashrae HOF 2001)	⑭ EXTERIOR WALL ACCENT FOR SCHOOL SIGNAGE
⑥ PREFINISHED PARAPET METAL CAP FLASHING w/ COUNTER FLASHING	⑮ STANDARD PORTABLE CLASSROOMS
⑦ PREFINISHED TRANSLUCENT WALL SYSTEMS ABOVE CLERESTORY LEVEL COMPLETE WITH RAIN SCREEN SYSTEMS	⑯ PORTABLE CLASSROOM STAIR c/w METAL RAILING
⑧ DOUBLE GLAZED, THERMALLY BROKEN ANODIZED ALUMINUM CURTAIN WALL EXTERIOR WINDOW AT ENTRY U VALUE=5.91 W/M2 R VALUE=1.47 (based on Ashrae HOF 2001)	⑰ PRESERVATIVE TREATED PLYWOOD EXTERIOR SKIRTING SYSTEMS
⑨ PREFINISHED HARDIE BOARD EXTERIOR WALL FINISH COLOUR #1	⑱ PORTABLE CLASSROOM EXIT DOOR
	⑳ PORTABLE CLASSROOM R.W.L.
	㉑ PREFINISHED CONCRETE MANSORY- SMOOTH FINISH BALL WALL-COLOR#1



RIGHT-SIDE ELEVATION

SCALE=1:300





REAR ELEVATION

SCALE=1:300

600 STUDENT CORE-MIDDLE SCHOOL ELEVATIONS

SCALE 1:300
DATE NOV.05,2008







A BUILDING SECTION
SCALE= 1:200

600 STUDENT CORE-MIDDLE SCHOOL
BUILDING SECTION


SCALE 1:100
DATE NOV.05,2008




ARCHITECTS
& INTERIOR
DESIGNERS



GYMNASIUM SECTION
SCALE= 1:50



TYPICAL CLASSROOM SECTION
SCALE= 1:50



TYPICAL MUSIC ROOM SECTION
SCALE= 1:50

KEYNOTES THIS SHEET ONLY:

- 1 SUSPENDED RADIANT PANEL
- 2 STEEL STUDS DEFLECTION TRACK
- 3 SUSPENDED ACOUSTIC TILE CEILING
- 4 ROOF STRUCTURE SEE STRUCTURAL DRAWINGS
- 5 DOUBLE GLAZED THERMALLY BROKEN CLEAR ANODIZED ALUMINUM CURTAIN WALL FRAME WINDOW W/OPERABLE WINNING UNIT
- 6 CONCRETE GRADE BEAM ON CONCRETE PILES (TBO)
- 7 16mm CEMENT BOARD ON 50mm Z-BARS, 50mm RIGID INSULATION, AIR/VAPOUR BARRIER TO FACE OF GRADE BEAM
- 8 FLOOR STRUCTURE SEE STRUCTURAL DRAWINGS
- 9 90mm CONCRETE BLOCK VENEER
- 10 190mm CONCRETE BLOCK
- 11 R20 INSULATION (REFER TO SECTION)
- 12 140 mm CONCRETE CHAMFER BLOCK SILL
- 13 PREFINISHED METAL CLADDING
- 14 AIR/VAPOUR BARRIER
- 15 PREFINISHED METAL FLASHING
- 16 PREFINISHED METAL CAP FLASHING c/w COUNTER FLASHING
- 17 ROOFING MEMBRANE ON FIBREBOARD POSITIVE SLOPE INSULATION

ROOF TYPE:

- R1 ROOF TYPE: R1
SBS TWO PLY ROOF MEMBRANE ON 25mm ASPHALT IMPREGNATED FIBREBOARD PROTECTIVE INSULATION POSITIVE SLOPED RIGID INSULATION (REQUIRED FOR BACK SLOPES ONLY) R30/RSI=5.28 RIGID INSULATION VAPOUR BARRIER MEMBRANE 13mm BENS DECK GYPSUM BOARD 38mm STEEL ROOF DECK ON STEEL STRUCTURE SLOPED TO DRAIN (REFER TO STRUCTURAL)

FLOOR TYPES:


- F1 FLOOR TYPE: F1
130mm REINFORCED CONCRETE FLOOR SLAB (EXACT THICKNESS TO BE CONFIRMED BY STRUCTURAL ENGINEER ON A SITE BASIS) 6mil. POLY VAPOUR BARRIER 50mm SAND UNDERBED 150mm MIN. FULLY COMPACTED GRANULAR FILL
- F2 FLOOR TYPE: F2
100mm CONCRETE TOPPING ON 38mm STEEL DECK ON STEEL STRUCTURE, REFER TO STRUCTURAL (RATED FOR 1.0 HOUR WHERE NOTED)
- F3 FLOOR TYPE: F3
19mm STRIP HARDWOOD FLOORING ON 2 LAYERS 13mm PLYWOOD SHEATHING ON CONTINUOUS WOOD SLEEPERS WITH BIO PADS @ 300mm O.C. POLY VAPOUR BARRIER / GROUND SHEET ON REINFORCED CONCRETE FLOOR SLAB ON GRADE, REFER TO STRUCTURAL COMPACTED SUBBASE (SUBSTRUCTURE PREPARED PER RECOMMENDATIONS CONTAINED IN GEOTECHNICAL ENGINEER'S REPORT

WALL TYPES:

- W1 WALL TYPE: W1
90mm ARCHITECTURAL BLOCK VENEER 38mm AIR SPACE R20/RSI=3.4 100mm STYROFOAM INSULATION AIR/VAPOUR BARRIER MEMBRANE 13mm EXTERIOR GRADE GYPSUM BOARD 150mm STEEL STUDS @400mm O.C. 16mm IMPACT RESISTANT GYPSUM BOARD
- W2 WALL TYPE: W2
PREFINISHED METAL CLADDING (ALLOW MIN. 19mm PROF 100mm GALVANIZED GIRTS @600mm O.C. R20/100mm ROXUL SEM-RIGID MINERAL FIBRE INSULATION AIR/VAPOUR BARRIER MEMBRANE 13mm EXTERIOR GRADE GYPSUM BOARD 150mm STEEL STUDS @400mm O.C. 16mm IMPACT RESISTANT GYPSUM BOARD
- W3 WALL TYPE: W3
CEMENT PARING 16mm CEMENT BOARD 50mm GALVANIZED Z' BARS 50mm RIGID INSULATION (REFER TO STRUCTURAL)
- W4 WALL TYPE: W4
PREFINISHED METAL CLADDING 100mm GALVANIZED GIRTS @600mm O.C. R20/100mm ROXUL SEM-RIGID MINERAL FIBRE INSULATION AIR/VAPOUR BARRIER MEMBRANE 190mm SMOOTH FACE CONCRETE BLOCK (PAINTED - EXPOSED BLOCK)
- W5 WALL TYPE: W5
90mm ARCHITECTURAL BLOCK VENEER 38mm AIR SPACE R20/RSI=3.4 100mm STYROFOAM INSULATION AIR/VAPOUR BARRIER MEMBRANE 190mm SMOOTH FACE CONCRETE BLOCK (PAINTED-EXPOSED BLOCK)

PARAPET ROOF TYPES:

- P1 PARAPET TYPE: P1
38mm PREFINISHED METAL CLADDING 100mm GALVANIZED GIRTS @600mm O.C. R20/100mm ROXUL SEM-RIGID MINERAL FIBRE INSULATION AIR/VAPOUR BARRIER MEMBRANE 13mm EXTERIOR GRADE GYPSUM BOARD 150mm STEEL STUDS @400mm O.C. (FULL VOID WITH BATT INSULATION) 16mm EXTERIOR GRADE PLYWOOD CARRY SBS TWO PLY ROOF MEMBRANE ROOFING FROM ROOF TO TOP OF WOOD COPING COUNTERFLASHING WITH PREFINISHED METAL COPING FLASHING (MIN. 2% SLOPE TO DRAIN)



600 STUDENT CORE-MIDDLE SCHOOL WALL SECTIONS

SCALE 1:50
DATE NOV.05,2008



ARCHITECTS & INTERIOR DESIGNERS

Appendix C – Design Ratios

Project Identification			
Project Name: Standard Core School 600 Capacity	Building Type: School		
Location: Base Case – Edmonton	Project Start Date: N/A		
School Board: N/A	Completion Date: N/A		
Architect: BARR RYDER ARCHITECTS	Market Condition: April 2007 Constant \$		
Constructor:	Geographic Location Factor: Edmonton Base Rate		
Description of Building		Building Area and Volume	
1 Storey w/ Mech. Mez.. Drilled Conc Piles, Grade Beams and Concrete Slab on Grade dependant on Soil conditions. Structural Metal Frame , <u>Ext Wall</u> : SS Framing, Ext. GB Sheathing, Air/Vapor Barrier Membrane, R20 Rigid Insulation. <u>Exterior Cladding</u> : 3.0 m Ht Masonry Facing, Upper Wall above 3.000 M Prefinished Metal Cladding, Double Glazed Thermally Broke Curtain Wall Exterior Windows, Alum. Curtain Wall at Entry, Modified SBS 2-ply Roof Membrane, <u>Int Partitions</u> Conc Blk :Corridors and High Maintenance Areas & GB/SS: All other Areas.	Gross Floor Area:	Core 4247m2	Built-out 5447m2
	Net Floor Area:	3844M2	4948m2
	Volume:	23384m3	27998m3
	Exterior Cladding:	1758m2	2198
	RooF Area:	4101m2	m2 5301m2
	No. of stories above grade:	1No.	1No.
	Modular Classrooms Built Out:	N/A	12 No.
Outline Specification		Ratios	
A10 Foundation: Piles with grade beams and pile caps for isolated columns, 130 slab on grade based on soils condition in area	Net Floor Area/GFA: Exterior Cladding Area/GFA: Window Area/GFA: Roof Area/GFA:	Core	Built-out
B10 Superstructure: Structural steel frame, steel beam interior structure, steel deck mezzanine. Loadbearing masonry at gymnasium.		.90:1	.90:1
B20 Exterior Enclosure: Wall Cladding is 3.0 m of masonry facing, metal siding finish, Aluminum frame punched windows, Curtain Wall At Entry, Modified SBS flat roofing system.		.41:1	.40:1
B30 Roofing: SBS 2 Ply		.06:1	.07:1
C10 Interior Construction: Concrete block partitions: Corridors and High Maintenance Areas. Impact resistant Gypsum Board and , SS partitions for the balance of the school	Capacities	Percentage exterior wall glazed: 14.6 %	
C30 Interior Finishes: Vinyl composite tile flooring to most areas, ceramic tile washrooms, carpet flooring to Library, admin and staff lounge, wood floor in gym, ceilings area a combination of painted drywall and acoustic tile, wall finish are predominantly paint, ceramic wall tiles at showers, urinals and mop sink.		Soil characteristics:	
D30 Mechanical: System utilizes interior air handling units and boilers, c/w perimeter radiant ceiling panels utilized for heating. Mechanical system is controlled using digital controls.		Density plumbing fixtures:	
D40 Fire Protection: Building is to be sprinklered.	Heating capacities:		
	Cooling capacities:		
	Ventilation Capacities:		
	Lighting intensity:		
Floor Area (by type)			
No.	Type	Core	Built-out
	Ancillary Classrooms/CTS	759m2	N/A
	Permanent Core Classrooms	743m2	
	Gymnasium	599m2	N/A
	Library	237m2	N/A
	Administration/Staff	289m2	N/A
	Storage	95m2	N/A
	Mech/Elect/Maintenance	153m2	N/A
	Circulation	658m2	N/A
	Other	714m2	N/A

Project Identification				
D50 Electrical: Main Service size to be confirmed during detail design. Service will be provided underground from a utility company network to a pad mounted transformer located adjacent to the building. From this transformer, an underground 347/600V three phase, four wire secondary power service will be provided to the electrical distribution center located in the main electrical room.		Modular Classrooms Built out	N/A	1200m2
Capital Cost of Permanent Core per m² (April 2007\$)	Gross Floor Area		4247m2	5447m2

Appendix D – LEED® Checklist

LEED Canada-NC 1.0 Project Checklist
Alberta Infrastructure Core G5-9 Middle School - 600 Capacity

Yes	? Probable	? Possible	No	
4	3	0	7	Sustainable Sites 14 Points

Y				
		?		
				X
				X
		?		
Y				
Y				
Y				
				X
				X
				X
				X
				X
				X
				X
		?		
Y				

Prereq 1 **Erosion & Sedimentation Control**
 Credit 1 **Site Selection**
 Credit 2 **Development Density**
 Credit 3 **Redevelopment of Contaminated Site**
 Credit 4.1 **Alternative Transportation, Public Transportation Access**
 Credit 4.2 **Alternative Transportation, Bicycle Storage & Changing Rooms**
 Credit 4.3 **Alternative Transportation, Alternative Fuel Vehicles**
 Credit 4.4 **Alternative Transportation, Parking Capacity**
 Credit 5.1 **Reduced Site Disturbance, Protect or Restore Open Space**
 Credit 5.2 **Reduced Site Disturbance, Development Footprint**
 Credit 6.1 **Stormwater Management, Rate and Quantity**
 Credit 6.2 **Stormwater Management, Treatment**
 Credit 7.1 **Heat Island Effect, Non-Roof**
 Credit 7.2 **Heat Island Effect, Roof**
 Credit 8 **Light Pollution Reduction**

Next Steps/Action Items:

Verify if site can achieve LEED criteria. PRIME

To be determined on a per site basis PRIME/AI

Ensure provision of showers for staff is acceptable to school boards (5% of FTE staff (not students) 1 shower per eight people). PRIME/AI

Review provision of Stalls allocated for electric or Hybrid cars with designated power outlets. School Board

Do not provide more parking than required by code. PRIME/AI

PRIME/AI

Cons. Eng

Cons. Eng

School Board or ASP

School Board or ASP

Cons. Eng

PVC roofs can achieve this LEED credit, SBS membranes can be used if suplimented with 18% of the roof having a higher reflectivity/Emissivity

Design lighting to meet LEED requirements. Cons. Eng

Yes	? Probable	? Possible	No	
4	0	0	1	Water Efficiency 5 Points

Y				
Y				
Y				
				X
Y				
Y				

Credit 1.1 **Water Efficient Landscaping, Reduce by 50%**
 Credit 1.2 **Water Efficient Landscaping, No Potable Use or No Irrigation**
 Credit 2 **Innovative Wastewater Technologies**
 Credit 3.1 **Water Use Reduction, 20% Reduction**
 Credit 3.2 **Water Use Reduction, 30% Reduction**

No irrigation to be provided in schools PRIME

No irrigation to be provided in schools PRIME

Use ultra low flow urinals and low flow toilets to achieve this credit Cons. Eng

Use ultra low flow urinals and low flow toilets to achieve this credit Cons. Eng

Yes	? Probable	? Possible	No	
8	1	7	0	Energy & Atmosphere 17 Points

Y				
Y				
Y				
Y				
6	0	4		
		?		
		?		
		?		
Y				

Prereq 1 **Fundamental Building Systems Commissioning**
 Prereq 2 **Minimum Energy Performance**
 Prereq 3 **CFC Reduction in HVAC&R Equipment**
 Credit 1 **Optimize Energy Performance**
 Credit 2.1 **Renewable Energy, 5%**
 Credit 2.2 **Renewable Energy, 10%**
 Credit 2.3 **Renewable Energy, 20%**
 Credit 3 **Best Practice Commissioning**

AI

Design building to achieve minimum of 6 EAc1 points and evaluate additional energy savings using a preliminary criteria of a 10 year simple payback. Conduct energy modeling as part of conceptual/schematic design. Cons. Eng

Design HVAC & fire protection without CFCs Cons. Eng

Design building to achieve minimum of 6 EAc1 points and evaluate additional energy savings using a preliminary criteria of a 10 year simple payback. Conduct energy modeling as part of conceptual/schematic design. Cons. Eng

Ensure AI are prepared to sign off on this. AI is currently doing most of the requirements of this credit AI

Y			
	?		

Credit 4 **Ozone Protection**
 Credit 5 **Measurement & Verification**
 Credit 6 **Green Power**

Design HVAC & fire protection without HCFCs
 Use AI DDC standards to achieve LEED M&V requirements
 School Boards may already be buying green power in order to achieve this credit. To be reviewed on a per site basis

Cons. Eng
 Cons. Eng
 School Board or ASP

Yes ? No

6 1 2 5

Materials & Resources

14 Points

Y			
			X
			X
			X
Y			
Y			
			X
			X
Y			
Y			
Y			
Y			
		?	
		?	
	?		

Prereq 1 **Storage & Collection of Recyclables**
Building Reuse:
 Credit 1.1 Maintain 75% of Existing Walls, Floors, and Roof
Building Reuse:
 Credit 1.2 Maintain 95% of Existing Walls, Floors, and Roof
Building Reuse:
 Credit 1.3 Maintain 50% of Interior Non-Structural Elements
 Credit 2.1 **Construction Waste Management:**
 Divert 50% from Landfill
 Credit 2.2 **Construction Waste Management:**
 Divert 75% from Landfill
 Credit 3.1 **Resource Reuse:** 5%
 Credit 3.2 **Resource Reuse:** 10%
 Credit 4.1 **Recycled Content:**
 7.5% (post-consumer + ½ post-industrial)
 Credit 4.2 **Recycled Content:**
 15% (post-consumer + ½ post-industrial)
 Credit 5.1 **Regional Materials:** 10% Extracted and Manufactured Regionally
 Credit 5.2 **Regional Materials:**
 20% Extracted and Manufactured Regionally
 Credit 6 **Rapidly Renewable Materials**
 Credit 7 **Certified Wood**
 Credit 8 **Durable Building**

Provide recycling areas as per LEED Reference Guide
 Divert 50% of Construction Waste from landfill
 Divert 75% of Construction Waste from landfill
 Analyze the most costly building materials in the project to determine if they can meet the 22.5% threshold for recycled materials and achieve this point and an ID point.
 Analyze the most costly building materials in the project to determine if they can meet the 22.5% threshold for recycled materials and achieve this point and an ID point.
 Analyze the most costly building materials in the project to determine if they can meet the 30% threshold for regional materials and achieve this point and an ID point.
 Analyze the most costly building materials in the project to determine if they can meet the 30% threshold for regional materials and achieve this point and an ID point.
 Hard to achieve but is doable
 Confirm if 50% of wood in the project could economically be certified wood
 Complete the LEED documentation spreadsheets and specify Quality Assurance requirements.

PRIME
 PRIME
 PRIME
 PRIME
 PRIME
 PRIME
 School Board or ASP
 PRIME
 PRIME

Yes ? No

14 1 0 0

Indoor Environmental Quality

15 Points

Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			
Y			

Prereq 1 **Minimum IAQ Performance**
 Prereq 2 **Environmental Tobacco Smoke (ETS) Control**
 Credit 1 **Carbon Dioxide (CO₂) Monitoring**
 Credit 2 **Ventilation Effectiveness**
 Credit 3.1 **Construction IAQ Management Plan:**
 During Construction
 Credit 3.2 **Construction IAQ Management Plan:** Testing Before Occupancy
 Credit 4.1 **Low-Emitting Materials:**
 Adhesives & Sealants
 Credit 4.2 **Low-Emitting Materials:**
 Paints and Coating
 Credit 4.3 **Low-Emitting Materials:**
 Carpet
 Credit 4.4 **Low-Emitting Materials:**
 Composite Wood and Laminate Adhesives
 Credit 5 **Indoor Chemical & Pollutant Source Control**
 Credit 6.1 **Controllability of Systems:**
 Perimeter Spaces
 Credit 6.2 **Controllability of Systems:**
 Non-Perimeter Spaces
 Credit 7.1 **Thermal Comfort:**
 Compliance

Required Design ventilation to meet ASHRAE 62.1-2004
 Required Ensure building is non-smoking
 1 Include CO2 sensors to control ventilation (i.e. vary ventilation to rooms based on CO2).
 1 Ensure ventilation effectiveness is achieved by delivering ventilation air at a low level.
 1 Incorporate the SMACNA and other requirements of this credit into the specification.
 1 Specify either IAQ testing or building flush out in the specifications.
 1 Specify low emitting adhesives & sealants in documents
 1 Specify low emitting paints & coatings in documents
 1 Specify low emitting carpets in documents
 1 Specify low emitting composite wood in documents
 1 Incorporate entrance way grills, MERV 13 filters & storage of hazardous material into the design.
 1 Incorporate lighting control & operable windows in design
 1 Incorporate lighting & ventilation control windows in design
 1 Design envelope and HVAC to meet ASHRAE Std. 55

Cons. Eng
 PRIME/AI
 Cons. Eng
 Cons. Eng
 PRIME & Cons. Eng
 PRIME & Cons. Eng
 PRIME & Cons. Eng
 PRIME
 PRIME
 PRIME & Cons. Eng
 PRIME & Cons. Eng
 Cons. Eng
 PRIME & Cons. Eng

Y			
Y			
	?		

Credit 7.2 **Thermal Comfort:** Monitoring
 Credit 8.1 **Daylight & Views:** Daylight 75% of Spaces
 Credit 8.2 **Daylight & Views:** Views 90% of Spaces

1 Utilize AI DDC standards to achieve LEED ASHRAE Std. 55 monitoring requirements.
 1 Ensure 75% of regularly occupied spaces are day lit
 1 Ensure 90% of regularly occupied spaces have views.

Cons. Eng
 PRIME
 PRIME

Yes ? No

3 2 0 0 Innovation & Design Process 5 Points

Y			
	?		
	?		
Y			
Y			

Credit 1.1 **Innovation in Design**
 Credit 1.2 **Innovation in Design**
 Credit 1.3 **Innovation in Design**
 Credit 1.4 **Innovation in Design**
 Credit 2 **LEED® Accredited Professional**

1 Incorporate requirements to use the building as a demonstration project (ex. signage, M&V readouts, window to see equipment, website, etc.)
 1 Contract documents to require 95% waste diversion to achieve an ID credit.
 1 Analyze whether MRc5 (regional materials) can reach 30% or MRc4 (recycled materials) can reach 22.5% to achieve an ID point.
 1 Use ultra low flow urinals and low flow toilets to achieve this credit
 1 Determine who will be the designated LEED AP on the project team.

PRIME
 PRIME
 PRIME
 Cons. Eng
 PRIME

Yes ? No

39 8 9 13 Project Totals (pre-certification estimates) 70 Points

Certified 26-32 points Silver 33-38 points Gold 39-51 points Platinum 52-70 points

AI Alberta Infrastructure
PRIME Prime Consultant
Cons. Eng Consulting Engineer
School Board School Board
ASP Alberta Schools Proponent

- ID1 Innovation Credits achieved on other projects**
- 1 Committing to use the project as a demonstration project
 - 2 Commitment to green cleaning products
 - 3 100% green power
 - 4 On site composting facility
 - 5 Low emitting materials - furniture
 - 6 Exceptional Water Use Reduction
 - 7 Exceptional CWM (i.e. >95%)
 - 8 Exceptional recycled materials (i.e. >22.5%)
 - 9 Exception regional materials (i.e. >30%)
- etc.